

BLOCK	A	B	C	TOTAL
[STILT FLOOR -1]	178.961	254.928	60.971	495.86 SQ.M.
[STILT FLOOR -2]	178.961	254.928	60.971	495.86 SQ.M.
GROUND FLOOR	2862.453	3071.008	977.84	6911.301
FIRST FLOOR	2862.453	3071.008	977.84	6911.301
SECOND FLOOR	2862.453	3071.008	977.84	6911.301
THIRD FLOOR	2862.453	3071.008	977.84	6911.301
FOURTH FLOOR	2862.453	3071.008	977.84	6911.301
FIFTH FLOOR	2862.453	3071.008	977.84	6911.301
SIXTH FLOOR	2862.453	3071.008	977.84	6911.301
SEVENTH FLOOR	2862.453	3071.008	977.84	6911.301
EIGHT FLOOR	2862.453	3071.008	977.84	6911.301
NINTH FLOOR	2862.453	3071.008	977.84	6911.301
TENTH FLOOR	2862.453	3071.008	977.84	6911.301
ELEVENTH FLOOR	2862.453	3071.008	977.84	6911.301
TWELFTH FLOOR	2862.453	3071.008	977.84	6911.301
THIRTEENTH FLOOR	2862.453	3071.008	977.84	6911.301
FOURTEENTH FLOOR	2862.453	3071.008	977.84	6911.301
FIFTEENTH FLOOR	2862.453	3071.008	977.84	6911.301
TOTAL F.A.R.	46159.17	32782.531	3055.462	82007.553

TOTAL F.A.R.GROUND TO FIFTEENTH FLOOR
82007.553 SQ.M. (EXCLUDING BASEMENTS) & S.I.H.

AT MATHURA ROAD, FARIDABAD

TOTAL F.A.R. GROUND TO FIFTEENTH FLOOR
8,217,000 S.F. (EXCLUDING BASEMENTS) 6.81/11

NOTES:

1. AUTOMATIC DETECTOR SYSTEM SHALL BE PROVIDED AS PER N.B.C.
2. AUTOMATIC ALARM SYSTEM SHALL BE N.B.C.
3. SEPARATE DUCT SHALL BE PROVIDED FOR ELECTRICAL FITTING AND FIRE FIGHTING INSULATION.
4. FIRE ESCAPE STAIRCASE SHALL BE 2 HOURS FIRE RATING.
5. ENTIRE BUILDING SHALL BE AUTOMATIC SPRINKLERED.
6. 1/G WATER TANK OF 200000LTS.
7. TERRACE TANK OF 20000 LITS.
8. TWO ELECTRICAL AND ONE DIESEL PUMP OF 2850 L.P.M. AND ONE ELECTRIC PUMP OF 180 L.P.M.
9. INTERNAL STAIRCASE SHALL BE AS PER N.B.C. CLOSURE NO. 4.9.
10. REFUGEE AREA SHALL BE PROVIDED AS PER N.B.C.
11. ALL FIRE PROTECTION SYSTEM SHALL BE AS PER N.B.C. AND FIRE FIGHTING EQUIPMENT SHALL BE OF ISI-MARKED.

BASICALLY ANNUAL DATA					
BLOCK	A	B	C	D	TOTAL
THIRD BAS.				2655.689	2655.68950.M
SEC. BAS.	6561.129	5825.70	1978.429	2655.689	17021.947 50.M
FIRST BAS.	6561.129	5825.70	1978.429	2655.689	17021.947 50.M
TOTAL	13122.26	11651.40	3956.858	7967.067	36702.46750.M

BLOCK-D (MULTI LEVEL PARKING) MECHANICAL PARKING	
FLOORS	AREAS DETAIL
GROUND FLOOR	2247.36 SQ.M.
FIRST FLOOR	2247.36 SQ.M.
SECOND FLOOR	2247.36 SQ.M.
THIRD FLOOR	2247.36 SQ.M.
FOURTH FLOOR	2247.36 SQ.M.
TOTAL	11236.80 SQ.M.

ALL FLOOR COVD AREA INCLUDING BASEMENTS+STILT
+MULTILEVEL PARKING FLOORS THAT IS
=13323.818SQ.M.+82007.553+36702.467+11236.80=
=143270.638 SQ.M. = (49586+49586+2247.36)

PARKING CALCULATION

TOTAL CAR = 572 SQ.M.

REQUIRED PARKING @ 40 SQ.M. OF COVD AREA =

$\frac{82007.810}{40} = 2050.587$ OR 2051 EGS

PROPOSED CAR PARKING

THIRD BASEMENT AREA=2655.89[MINUS 15% AREA FOR SERVICES]

=2257.335 SQ.M. = 64.56 OR 65 NOS.

35

SECOND BASEMENT AREA=17021.947[MINUS 15% AREA FOR SERVICES]

=14468.854 SQ.M. = 413.52 OR 413 NOS.

35

FIRST BASEMENT AREA=17021.947[MINUS 15% AREA FOR SERVICES]

=14468.854 SQ.M. = 413.52 OR 413 NOS.

35

STLT LEVEL = 22152.816 SQ.M. = 738.90 OR 739 NOS.

30

MULTI LEVEL PARKING = 11236.80 SQ.M. = 374.56 OR 375 NOS.

30

SURFACE PAR. = $\frac{1142.94 + 18 + 85}{2} = \frac{1248.24 + 19 + 37 + 11}{2} = 115$ NOS

TOTAL PROPOSED PARKING = 65+413+413+739+375+115 = 2122 NOS.

K
PROPOSED AREA IN COMM. = 1977.048 sq. ft.
PROPOSED AREA IN LT. (Rd) = 8207.553 - 1977.048
= 6230.505 sq. ft.
COMM. AREA DETAIL = GRD. FLOOR = 954.082
CHL.
FIRST FLOOR = 1092.166
1977.048 sq. ft.

OWNERS SEAL & SIGNATURE

For DOVE INFRASTRUCTURE PVT. LTD.

ARCHITECTS SEAL & SIGNATURE

Checked and found ok for
Public Health (Informal) Services
patent right to governments in

Superintending Engineer (H
HUDA, Faridkula

PROJECT :
I.T PARK MEASURING 8.5 ACES IN REVENUE
ESTATE OF VILLAGE ANANGPUR, TEHSIL AND
DISTRICT FARIDABAD, HARYANA.
BELONGS TO M/S.DOVE INFRASTRUCTURE PVT.LTD.

SANCTIONED

FOR: M/S DOVE INFRASTRUCTURE PVT. LTD.

DRAWING TITLE

SITE PLAN

DATE: APRIL -2000

SCALE: 1:400

DRAWING NO.

01

